

Performance Bond may be required per MCA 18-2-201

Prevailing Wages may be required per MCA 18-2-422 18-2-401

Specifications for Fairgrounds Exhibit and 4H Building: Remove and replace existing tin roof and install new soffit, fascia, and gutters including endcaps and drip edge.

Bids are requested for labor and materials. Project can commence immediately, but must work around scheduled events at the fairgrounds. It is strongly suggested that interested contractors see the project. Award bid will include totaled labor costs for the following tasks:

- Removal of existing roof and replace with like, commercial grade/29 gauge
- Cap and cover all roof façade
- Install new soffit and fascia
- Install new gutters and downspouts
- Disposal of all construction debris from site
- Separate costs for Exhibit and 4H building

Specifications for Disaster Emergency Services Building: Remove and replace existing tin roof and install new soffit, fascia, and gutters including endcaps and drip edge.

Bids are requested for labor and materials. Project can commence immediately, but must work around scheduled events at the fairgrounds. It is strongly suggested that interested contractors see the project. Award bid will include totaled labor costs for the following tasks:

- Removal of existing roof of lower level lean to and replace with pitched tin roof, commercial grade/29 gauge
- Cap and cover all roof façade
- Install new soffit and fascia
- Install new gutters and downspouts
- Disposal of all construction debris from site